

October 15, 2014

Combi Systems: Lessons Learned from the Field



2015 ACEEE Hot Water Forum

Ben Schoenbauer

Senior Research Engineer


Center for Energy and Environment



Sponsors and Partners

- NorthernSTAR - A DOE Building America Research Team
- Sustainable Energy Resources for Consumers Grants



- Center for Energy and Environment
- Sustainable Resources Center
- University of Minnesota
- The Energy Conservatory





Introduction to Combi Systems

- Integrated space heating and domestic hot water
- Two main types:
 - Hydronic space heating
 - Forced-air space heating
- New equipment has several advantages
 - High efficiency
 - Wide range of loads
 - Sealed combustion

COMBINED WATER AND SPACE HEATER USING STORAGE WATER HEATER





Our project

- Low income weatherization
 - Orphaned water heaters
- Focus on Natural Gas Forced Air Systems
- Laboratory Testing
 - Support of Implementation
- **Field Implementation – 200+ homes**
 - Low income weatherization in Minnesota
- **Detailed Field Study – 20 homes**
 - Representative sample of implementation




Lessons Learned

- Installation
- Optimization
- Operation
- Programs/Rebates
- Cost
- Future



Installation



- Venting
- Mixing valve
- Condensate pump
- Air handler flow rate control valve
- Sizing






No Optimization

(for a 40,000 Btu/hr design load)





Right Sizing









Occupant Experience

- Changes to:
 - Water Delivery
 - Air Delivery




Water Temperature Delivery





Delivered Air Temperature


Existing Furnace - 1027



- Lower air temperatures
- Longer cycles



Savings



Heating Plant	Installed Efficiency			Rated Efficiency	
	Annual	Winter Space Heat	Summer DHW	Rating Method	Rating
StWH	86%	87%	60%	Thermal Efficiency	95%
TWH	86%	85%	85%	Energy Factor	93%
HWH	90%	92%	61%	Energy Factor	95%
Existing ¹	71%	72%	47%	AFUE/Energy Factor	79% / 59%



Verification

- 3 Tiers of Verification

Verification Measures			Expected Performance	
Approved Equipment	Trained Contractor	Verified Performance	Space Heat	DHW
✓			80% of Optimal	Optimal
✓	✓		90% of Optimal	Optimal
✓	✓	✓	Optimal	Optimal



Energy Savings Verification

- LIWX agency installed 200+ in Twin Cities metro
- Typically replaced a 80% AFUE furnace and a 0.59 EF water heater
- Trained technician performed system optimization
 - Utility bills showed an median savings of 13%
- Detailed pre/post analysis
- Trained optimization and verification
 - Savings of 16%




Future

- Total system packages
- Controls
 - Set point reduction

Site	Heating Plant	Set Point Reduction	Annual Energy Use (therms)			
			Pre	Post	Savings	
1027	Polaris	10	809	776	33	4.1%
1031	Polaris	5	773	751	22	2.8%
1056	Phoenix	10	551	538	14	2.5%

- Full modulation




THANK
you!

www.mncee.org/dia



Installed Performance





Lessons Learned

- Assessing the needs of the home and letting that inform the system that is installed
 - number people and showers and how that effects comfort
 - water quality
 - thermostat set points and setbacks
- Code officials
 - ask first, install second!
 - System diagrams




Lessons Learned

- Having good contractors
 - learning curve
 - Training
- Ensuring quality of installation
 - equipment specific requirements
 - field verification of installation
 - optimization and maintenance



Cost





Utility Billing Analysis

