

# CO2 Combi System Compared to Other Systems in the PNNL Lab Homes

Cheryn Metzger, Joe Petersen, Josh McIntosh Pacific Northwest National Laboratory

Ken Eklund Washington State University March 21st, 2018 Portland, OR




# **BACKGROUND**

### Benefits: CO<sub>2</sub> as a Refrigerant (R744)



- Thermal lift at cold temperatures exceeds standard refrigerant capacity
- Flexible in different climate zones
- Non-flammable
- Global Warming Potential of 1 (vs 2,088)







Experiment Metric	Unitary System	Split-System
Dispatchable Power (kW)	1.3	1.2
Recovery Energy Shift (kWh)*	2.65	2.95
Oversupply duration (hours)	6	6
Maximum off period while delivered temperature is met (hours)	6	12

<sup>\*</sup>Energy required to recover tank to set point after DR event


Opportunity!

GP Sullivan and JP Petersen. July 2015. <u>Demand-Response Performance</u> <u>of Sanden Unitary and Split-System Heat Pump Water Heaters</u>. PNNL - 24224, Pacific Northwest National Laboratory, Richland, WA.

### **Project Participants**



Proudly Operated by Battelle Since 1965





# **EXPERIMENTAL PLAN**

### **Lab Homes Characteristics**



Proudly Operated by Battelle Since 1965

- Represent existing homes
  - 3 BR/2BA 1493-ft² double-wide, factory-built to HUD code
  - All-electric with 13 SEER/7.7 HSPF heat pump central HVAC + alternate Cadet fan wall heaters throughout
  - R-22 floors, R-11 walls & R-22 ceiling with composition roof
  - Incandescent lighting
  - Bath, kitchen, whole-house exhaust fans
  - Carpet + vinyl flooring
  - All electric
- Modifications include end-use metering, sensors, weather station, and three electric vehicle charging stations





### **Research Questions**



### During the heating season:

- 1. Does the system meet common space and water heating loads in these homes?
- 2. What is the impact on the system's ability to meet space and water heating needs when occupant-controlled variables such as thermostat settings, hot water draws, and hot water temperature settings are moved beyond average?
- 3. What is the DR oversupply mitigation capability and its ability to meet space and water heating loads?
  - a. When occupant-controlled variables are moved beyond average?

3/26/2018

### **Load Definitions**



Proudly Operated by Battelle Since 1965

Thermostat settings

Low: 65°F

Medium: 71°F

■ High: 80°F

Water Temperature settings:

Low: 125°F

High: 135°F

Water Load settings:

Low: 24 gpd

Medium: 46 gpd

High: 85 gpd

March 26, 2018




**EXPERIMENTAL SETUP** 



### **Experimental Setup**




Proudly Operated by Battelle Since 1965



System design credit to Mark Jerome, CLEAResult





From heat pump


Pressure relief valve

To heat pump

# Interior Heat Exchange System with Electric Forced Air Furnace



Proudly Operated by Battelle Since 1965





# **HIGH LEVEL RESULTS**

### **Occupancy Load Results**



- When outdoor temp is above 40°F, system can meet loads:
  - 85 GPD
  - 80°F thermostat set point
  - 135°F water heater set point
- System cannot meet loads consistently:
  - When outdoor temperature is below 40°F
- Inconclusive if system can meet loads consistently following a DR event if temperatures are above 40°F
- System favors space conditioning temperature over water heating temperature



# **ENERGY USE DATA**


March 26, 2018

### **Combi Energy Use**



Proudly Operated by Battelle Since 1965

- ▶ 71°F Indoor temperature set point
- 125°F Hot water set point
- 46 gallons per day





## **COMPARED TO PAST DATA**


March 26, 2018

### **Past Experiment Results**




- 71°F Indoor temperature set point
- 125°F Hot water set point
- 130 gallons per day

### **Electric Forced Air Furnace and HPWH (in different modes)**



► Total energy use per outdoor degree increases




### **Upcoming Webinar!**



Proudly Operated by Battelle Since 1965

https://www.publicpower.org/event/field-demonstration-co2-waterspace-heating-combination-system





### **THANK YOU!**

Contact Information:
Cheryn Metzger PE PMP LEED AP
Cheryn.metzger@pnnl.gov
707-623-7091

https://labhomes.pnnl.gov/

Let me know if you would like to be added to the Lab Homes Newsletter!