

Residential Combi-Space/Water Heating Gas Absorption Heat Pump System:

Field Evaluation and Lessons Learned

Stone Mountain Technologies, Inc.

Johnson City, TN

Michael Garrabrant, President

www.stonemountaintechnologies.com

ACEE Hot Water Forum

Portland, OR


February, 2017



Topics of Discussion


- ❖ GAHP Technology Background
- ❖ GAHP Combi Demonstration
 - ❖ Preliminary Results
- ❖ Lessons Learned and Next Steps

GAHPs: Efficiency Leap for Heating




- ❖ Work well at low outside temperatures (back-up not required)

How Does It Work?



$$\text{COP}_h = Q_{\text{cond}}/E_{\text{in}} = 3.0\text{-}4.0$$

$$Q_{\text{heat}} = \sim 1.1 \times Q_{\text{cooling}}$$




$$\text{COP}_h = (Q_{\text{cond}} + Q_{\text{abs}})/Q_{\text{in}} = 1.4\text{-}2.0$$

$$Q_{\text{heat}} = (Q_{\text{cond}} + Q_{\text{abs}}) \sim 2.5 \text{ times } Q_{\text{evap}}$$

Capacity & COP Remain High at Low Ambient Temperatures

Gas Absorption's Renewable Energy Content: 35%



SMTI Gas Absorption Heat Pumps

$$\text{COP}_{\text{HHV}} = 1.4 \text{ at } 47/120^{\circ}\text{F}$$

- ❖ Gas-Fired, Air to Water Heat Pump
- ❖ Condensing
- ❖ 4:1 Modulation

- ❖ 10,000 to 140,000 Bth Heating Output Models
- ❖ 20° F Hydronic Differential
- ❖ Outdoor Installation (no venting)
- ❖ SCAQMD NOx Compliant




Forced-Air Space Heating

Heating Dominated Climate Zones: 4000+ HDD

Ultimate Comfort Solution

Supply Air Function
of Ambient, >100°F

Modulating or
Multi-Speed
Air-handler



CLIMATE ZONE MAP




4:1 Modulating
Heat Pump
with
Ambient Set-Back


Outdoor Location
for Safety

Residential Space Heating

Heating Dominated Climate Zones: 4000+ HDD




Combi




Hydronic Zoned
(radiant, 'mini-split', etc)
(can also be Combi)


Source Energy and CO₂ Advantage



Source Energy and CO₂ Advantage



Cost Per Delivered Therm of Heat



GAHP Development Status

10,000 btu/hr



Field Testing

80,000 btu/hr



Field Testing

140,000 btu/hr



Lab Testing



SMTI Gas Absorption Heat Pumps - AFUE

AFUE for Region IV: 139%

80,000 Btu/hr "Beta 2" Prototype

Rating Point	Actual Ambient Temperature (°F, dry bulb)	Actual Ambient Humidity (°F, dew point)	Actual Hydronic Return Temperature (°F)	Firing Rate (Btu/hr)	Output (Btu/hr)	COP_Gas	Measured Power Draw (W)
1	45.1	31.1	95.5	14313	20233	1.41	309.0
2	32.8	30.8	95.2	13728	18609	1.36	315.7
3	14.7	2.3	94.8	15232	19322	1.27	335.1
4	14.8	12.2	95.3	34317	46601	1.36	438.7
5	33.0	28.3	94.9	55537	77778	1.40	591.9
6	14.4	12.2	94.6	55737	74875	1.34	611.9
7	4.9	3.4	94.4	56871	72339	1.27	604.7

Data courtesy of GTI

ANSI Z21.40.4 Performance Testing & Rating Gas-Fired Air-Conditioning and Heat Pump Appliances

Residential Combi Demonstration


- ❖ Single family home in Northeast TN
- ❖ GAHP unit provides space and domestic hot water heating
- ❖ 2,200 sqft, built 1947
- ❖ 3.5 Occupants

- ❖ GAHP Replaced
 - ❖ 80,000 Btu/hr 90% Furnace
 - ❖ 50 gal Electric Water Heater

- ❖ March, 2016 Installation
- ❖ M&V by GTI



Residential Combi Demonstration



Programmable Thermostat with 3 Heating Mode Settings
Heating Mode Determines Fan Speed: High/Med/Low

Residential Combi Demonstration



← **Alpha 80K GAHP**

Installed from March 2016
through October 2016



Beta 80K GAHP →

Installed from November 2016
to present



2016/2017 Heating Season to Date

❖ 373 gallons of DHW drawn on average per week - 54 gallons per day for household (3.5 occupants)




$$GOP_Gas = (GAHP_output)/(Input)$$

*Utilization defined as $(GAHP_output)/(Gas + Electricity\ Input)$

Note: Unit serviced from 12/21/2016 to 1/10/2017

Residential Combi Field Test




Data courtesy of GTI


Residential Combi: Data Snap Shot

24 hour operating period (December 10, 2016)

- ❖ GAHP able to heat home quickly after nighttime set-back switch
- ❖ Supply air temps above 105°F (above 110°F for all but 1 run)
- ❖ Potential to reduce ambient setback curve
- ❖ 10 total cycles



Residential Combi: Data Snap Shot



Data courtesy of GTI

Lessons Learned – Hydronic Loop

Minimize Hydronic Loop Volume

- ❖ Field test loop volume is large (~15 gallons)
- ❖ High Cycling Losses (energy used to heat loop volume but not fully utilized)
- ❖ Most significant during summer, with water heating only
- ❖ Switching from 1" ID tube to 0.75" ID tube reduces charge volume by 42%
- ❖ Balance hydronic loop volume and required pump power

Lessons Learned – Hydronic Loop Volume





Water Heater Only Cycles, Data Courtesy of GTI

Lessons Learned – Storage Tank

Size/Performance of Indirect Coil Critical

- ❖ **First Tank:** 45 gallon, internal coil 11.1 ft², T-stat located low in tank
 - ❖ Short cycles (6-8 gallons heated), high hydronic temperatures required
 - ❖ More energy to heat hydronic loop than to heat water in tank!
- ❖ **Second Tank:** 80 gallon, internal coil 18 ft², T-stat above coil
 - ❖ Longer cycles (18-25 gallons heated), lower hydronic temperatures required



Lessons Learned - AHU

Air-Handler Capacity & Modulation Must Match GAHP

- ❖ 5 speed Hydronic AHU (limited to 3 speeds by T-stat)
- ❖ Low Speed: Provides heating capacity >4:1
 - ❖ Unless hydronic supply temperature low → low supply air temps
- ❖ Increased cycling of the GAHP, lower avg cycle COPs

- ❖ Modulating Blower Preferred
- ❖ Lowest Speed Must Result in 4:1 Modulation
Will allow for longer cycles at lower speeds

Developments: AHU under development
at SMTI using ECM blower



Lessons Learned –System Controls

- ❖ Thermostat Settings
- ❖ On/Off Timing of AHU/Pump/GAHP
- ❖ Ambient Set-Back Curve
- ❖ Space & Water Heating Modes

Summary

GAHPs offer significant potential for energy and cost savings with an AFUE of 139% (Region IV)

HOWEVER,

This savings can only be maximized when auxiliary systems are designed for operation with a GAHP

Next Steps in 2017

- 3-6 Residential combi field tests (pending)
- Two full service restaurant field tests in Los Angeles, California (Water heating and kitchen cooling)
- Commercial water heating field test in Tennessee
- Six residential water heater field tests in Los Angeles, California
- 5 kW Residential Combi Prototype
- Beta engine waste heat driven chiller for military and disaster relief applications

Acknowledgments

- ❖ NEEA
- ❖ Gas Technology Institute
- ❖ US Department of Energy

- ❖ Special Thanks to Paul Glanville, GTI

Thank You!

Michael Garrabrant

mgarrabrant@stonemountaintechnologies.com

www.stonemountaintechnologies.com