# 3C: Gas Heat Pump Water Heating in Commercial Laundries

#### **Stone Mountain Technologies, Inc.**

Johnson City, TN Michael Garrabrant, President Dr Christopher Keinath, Director Engineering

> ACEEE Hot Water Forum Portland, OR March, 2018



## **Commercial Laundry Overview**

- Commercial Laundries, or "On Premise Laundries" Use A Lot of Hot Water & Energy
- Hotels, Prisons, Universities, Nursing Homes, Hospitals and "Industrial"
- > 140-170°F Temperature

## **Commercial Laundry Overview**

- > Washer-Extractor
  - > ~3-4 gallons per lbm
  - > 35 800 lbm models
- > Tunnel Washers
  - ~2 gallons per lbm
- Set of Queen-Size Sheets
  ~3 lbs






## **Commercial Laundry Overview**

- Gas Boilers at 78-92%
  Efficiency
- Very large, consistent, year-round hot water demands

Excellent Opportunity for Gas Absorption Heat Pumps to Reduce Energy Use




# **Gas-Fired Absorption Heat Pump**



\*\* Natural Gas, Propane, Fuel Oil, BioDiesel, Renewable Gas, etc.

## How Does It Work?



#### Capacity & COP Remain High at Low Ambient Temperatures

# **SMTI** Gas Absorption Heat Pumps

## $COP_{HHV} = 1.45 \text{ at } 47/120^{\circ}F$

- \* Gas-Fired, Air to Water Heat Pump
- Condensing
- 4:1 Modulation
- \* 10,000 to 140,000 Bth Heating Output Models
- 20° F Hydronic Differential
- Outdoor Installation (no venting)
- SCAQMD NOx Compliant
- ✤ GWP = 0



**Patents Pending** 

# Family of GAHP Models

10 kBth

#### 20 kBth

#### 80 kBth

#### 140 kBth









#### **Anything In-Between**








# **Commercial Laundry Field Test**

## **Commercial Laundry Facility**


- Laundry facility owns and washes linens (sheets, robes, etc.) for surrounding health care facilities
- > Operating 2 shifts, 6 days per week
- > Total facility uses roughly 50-60K gallons of hot water daily
- System targeted for GAHP field install estimated to use 10K-20K gallons of hot water daily



## Current Boiler Based Water Heating System



#### Current Boiler Based Water Heating System




#### Baseline Monitoring of Hot Water Usage

- Bypass loop installed between two storage tanks
- Flow meter installed in loop





#### Baseline Monitoring of Hot Water Usage



~50 draws per 8 hrs | ~ 70 gpm (~160 gal/draw)




#### Baseline Monitoring of Hot Water Usage

- ➢ Hot Water Outlet: 153 167° F
- Cold Water Inlet: 53 55° F
- ~ 140 therms hot water/day
- ~ 180 therms gas/day
- ≻ ~ \$160/day
- ➤ ~ \$50,000/year

## Field Installed GAHP System

GAHP will preheat water before flow to steam heated tank

GAHP should provide almost continuous baseload water heating




# Field Installed GAHP

# GAHP skid to be installed in late March 2018




Lochinvar SET 119 Indirect Tanks



## 140 kBtu/hr GAHP "Beta 2"

Beta 2 is highest performing 140K prototype to date

> COP of 1.44 at 47/100°F design



# Estimated Energy and Cost Savings

For Single 140 kbth GAHP prototype installed at field test site

#### **Assumptions:**

- ➢ GAHP COP of 1.4
- Boiler COP of 0.8
- > Natural Gas: \$0.904 per therm
- Electric cost: \$0.10 per kWhr

#### **Anticipated Economics:**

Gas Therms Saved/Year:	3744
Gas Savings/Year:	\$3,385
kWhr Used/Year:	2000
kWhr Cost/Year:	\$200
Net Savings/Year:	\$3,185
Simple Payback:	~3.5 years (one 140 kBth GAHP)
	~2.8 years (two 140 kBth GAHPs)



- Commercial laundry facilities are significant consumers of hot water
- Baseline monitoring of field test with GAHP providing baseline heating underway
- Commercial GAHP water heaters have the potential to significantly reduce energy use and operating cost
- Reasonable paybacks expected based on yearly savings

## Other GAHP Projects in 2018

- ✤ 3 residential <u>combi</u> field tests in cold climate regions
- 2 full-service restaurant water heating/space cooling field tests in Los Angeles
- Six residential water heater field tests in Los Angeles
- Multi-family <u>combi</u> field test in Chicago
- 20 kbtu/hr residential combi prototype (net zero energy)
- Fuel-oil / Bio-diesel residential combi prototype

#### Acknowledgments

#### Work Performed Under a CRADA with ORNL









# **Thank You!**

Michael Garrabrant mgarrabrant@stonemtntechnologies.com www.stonemountaintechnologies.com